

THE CORPORATION OF THE CITY OF VERNON

# POLSON PARK NATURALIZATION PHASE 2

ISSUED FOR PROPOSAL

JANUARY 29, 2024


Project Number: 111710119

Contract Number: 23-100-INF

### **DRAWING LIST** <u>GENERAL</u> FRUIT UNION G001 COVER PLAZA G002 DRAWING LIST & PROJECT LOCATION HWY 6 G003 G004 GENERAL NOTES & MATERIAL SIZING ~ PROJECT LOCATION <u>CIVIL</u> C104 KEY PLAN EXISTING SITE PLAN C105 POLSON C106 PROPOSED SITE PLAN C112 REMOVALS PLAN PARK 24 AVE C205 CHANNEL PLAN / PROFILE STA 1+900 - 2+070 C206 CHANNEL PLAN / PROFILE STA 2+070 - 2+260 C207 CHANNEL PLAN / PROFILE REACH 2 DOWNSTREAM CHANNEL TIE-IN C215 PEDESTRIAN BRIDGE PLAN / PROFILE C216 PEDESTRIAN BRIDGE PLAN / PROFILE C225 MULTI-USE PATHWAY PLAN / PROFILE STA 1+000 - 1+140 JUBILEE C226 MULTI-USE PATHWAY PLAN / PROFILE STA 1+140 - 1+290 HOSPITAL C227 MULTI-USE PATHWAY PLAN / PROFILE STA 1+290 - 1+345 C250 GRAVEL PATHWAY PLAN / PROFILE STA 1+000 - 1+110 GRAVEL PATHWAY PLAN / PROFILE STA 2+000 - 2+130 C251 C252 GRAVEL PATHWAY PLAN / PROFILE STA 2+130 - 2+260 C310 SECTIONS POLSON C311 SECTIONS MALL C312 SECTIONS C313 SECTIONS 19 AVE C314 SECTIONS C501 TYPICAL CHANNEL DETAILS C502 TYPICAL CHANNEL DETAILS C503 TYPICAL CHANNEL DETAILS 18 AVE C504 TYPICAL CHANNEL DETAILS POTTERY RD C610 PLANTING PLAN 16 AVE C611 PLANTING PLAN C612 PLANTING DETAILS 15 AVE C702 TRAFFIC MANAGEMENT PLAN STRUCTURAL BRIDGE GENERAL NOTES S101 S102 16 METRE PEDESTRIAN BRIDGE S103 8 METRE MIXED USE BRIDGE **LANDSCAPE** DND DND LANDSCAPE HYDROSEEDING KEY PLAN L200 L201 LANDSCAPE PLANTING KEY PLAN L202 LANDSCAPE PLANTING CHANNEL PLAN - EAST L203 LANDSCAPE PLANTING CHANNEL PLAN - CENTRAL 11 AVE L204 LANDSCAPE PLANTING CHANNEL PLAN - WEST LOCATION PLAN DRAWING NUMBER DESIGNATION DRAWING SEQUENCE **DISCIPLINE DESIGNATORS** 000 - GENERAL (SYMBOLS, LEGEND, NOTES, ETC.) 100 - PLANS (HORIZONTAL VIEWS) G GENERAL 200 - ELEVATIONS (VERTICAL VIEWS) LANDSCAPE **IRRIGATION** 300 - SECTIONS (TYPICAL SECTION VIEWS) E ELECTRICAL 400 - GEOMETRIC VIEWS (DETAILED ROAD GEOMETRIC PLANS AND TABLES) 500 - SECTIONS AND DETAILS (SECTIONAL VIEWS, WALL SECTIONS, DETAILS) 600 - PAVEMENT MARKINGS AND SIGNAGE PLANS 700 - TRAFFIC MANAGEMENT PLANS | ISSUE No. | DATE | DESIGNED | DRAWN | CHECKED | **DESCRIPTION**











ENGINEERING AND GIS SERVICES



DRAWING LIST & PROJECT LOCATION

**SHEET**2 **OF** 

POLSON PARK NATURALIZATION PHASE 2



2. ALL DIMENSIONS ARE IN METRES AND MILLIMETRES UNLESS OTHERWISE NOTED. WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS.

- 3. CONTRACTOR IS RESPONSIBLE TO CONFIRM THE LOCATION OF ALL UTILITIES ON SITE PRIOR TO CONSTRUCTION. VERIFY LOCATION AND DEPTH OF ALL UTILITIES PRIOR TO COMMENCING WORK. CONTRACTOR IS RESPONSIBLE TO CALL FOR UTILITY LOCATES AND ANY COSTS TO REPAIR DAMAGE DUE TO FAILURE OF THE CONTRACTOR TO LOCATE EXISTING UTILITIES SHALL BE BORNE BY THE CONTRACTOR. CONTRACTOR SHALL BE RESPONSIBLE FOR SECURING ALL NECESSARY PERMITS AND SHALL NOTIFY ALL UTILITY COMPANIES WITH UTILITIES ON SITE PRIOR TO THE CONSTRUCTION OF THE PROJECT. CONTRACTOR SHALL ADHERE TO ALL APPLICABLE LOCAL, PROVINCIAL AND/OR FEDERAL LAWS OR REGULATIONS.
- 4. CONTRACTOR IS RESPONSIBLE TO ENSURE ALL SETBACKS FROM UTILITIES, APPURANCE, STRUCTURES AND HARDSCAPE ARE PER GOVERNING MUNICIPAL STANDARDS.
- 5. THE CONTRACTOR SHALL VERIFY ALL EXISTING GRADES AND SITE CONDITIONS ON THE PROJECT SITE BY FIELD INSPECTION BEFORE SUBMITTING A BID. THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF TREES, SHRUBS, AND PLANT MATERIAL WITHIN THE LIMITS OF WORK AREA THAT ARE TO REMAIN IN PLACE. ANY EXISTING PLANT MATERIAL DAMAGED WILL BE REPLACED BY THE CONTRACTOR WITH "AS-EQUAL" MATERIAL AS APPROVED BY THE CONTRACT ADMINISTRATOR.
- 6. CONTRACTOR SHALL REPAIR ALL DAMAGE, TO AT MINIMUM A PRE-CONSTRUCTION CONDITION OR BETTER. TO ALL EXISTING FACILITIES/UTILITIES/STRUCTURES CAUSED BY THEIR WORK AT THEIR OWN EXPENSE. CONTRACTOR SHALL PROVIDE PROTECTION TO PRIVATE AND PUBLIC PROPERTY AND UNDERGROUND SERVICES. A DIGITAL PHOTO RECORD OF ALL EXISTING DAMAGE TO THE SITE PRIOR TO CONSTRUCTION IS TO BE SUBMITTED TO THE CONTRACT ADMINISTRATOR BEFORE COMMENCEMENT OF ANY WORK ON THE SITE.
- 7. THE SECURITY OF THE SITE IS THE RESPONSIBILITY OF THE CONTRACTOR DURING CONSTRUCTION. DURING CRITICAL PERIODS, SUCH AS ENSURING FINISHED SURFACES AND LINE MARKINGS ARE NOT DRIVEN ACROSS OR OTHERWISE VANDALIZED, SITE SECURITY IS TO BE MAINTAINED.
- 8. THE CONTRACTOR SHALL RESTORE ALL AREAS OF INTENTIONAL DISTURBANCE AS PER THE PLANTING PLAN DRAWINGS. AREAS OF UNINTENTIONAL DISTURBANCE ARE TO BE RESTORED AT A MINIMUM TO PRE-CONSTRUCTION CONDITIONS UNDER THE GUIDANCE OF A QUALIFIED ENVIRONMENTAL PROFESSIONAL (QEP).
- 9. THE CONTRACTOR SHALL SUPPLY ALL MATERIAL, LABOR AND OTHER IN QUANTITIES SUFFICIENT TO COMPLETE WORK SHOWN WITHIN THESE DRAWINGS. ANY AMBIGUITY IN THE DRAWINGS, SPECIFICATIONS, OR DETAILS IS TO BE REPORTED PRIOR TO THE START OF ANY WORK. ANY DISCREPANCIES BETWEEN QUANTITIES SHOWN AND ACTUAL SHALL BE REPORTED TO THE CONTRACT ADMINISTRATOR
- 10. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS FROM THE GOVERNING MUNICIPALITY OR APPROVAL AUTHORITY PRIOR TO CONSTRUCTION FOR ALL ON-SITE AND OFFSITE IMPROVEMENTS OUTLINED WITHIN THIS SET OF PLANS AND/OR ANY OTHER ADDITIONAL WORK THEY MAY PERFORM IN THE INTEREST OF THIS PROJECT.
- 11. ALL TESTING OF MATERIALS, COMPACTION TESTING AND ALL ASSOCIATED COSTS FOR TESTING ARE THE RESPONSIBILITY OF THE CONTRACTOR, UNLESS OTHERWISE INDICATED IN THE CONTRACT DOCUMENTS. THE ITEMS REQUIRING TESTING ARE TO BE IDENTIFIED IN THE CONSTRUCTION DRAWINGS AND SPECIFICATIONS, TEST RESULTS FOR THE PROJECT PROVING ALL REQUIREMENTS HAVE BEEN MET ARE TO BE SUBMITTED ELECTRONICALLY TO THE CONTRACT ADMINISTRATOR.
- 12. THE CONTRACTOR IS RESPONSIBLE FOR ALL SURVEYING FOR THE PROJECT. AN ACCURATE LOG OF CONTROL AND SURVEY WORK IS TO BE MAINTAINED AS THE PROJECT PROGRESSES. PRIOR TO START OF CONSTRUCTION THE NAME AND ADDRESS OF THE SURVEYOR IS TO BE SUBMITTED TO THE CONTRACT ADMINISTRATOR FOR APPROVAL. DURING CONSTRUCTION THE SURVEYOR MUST BE PREPARED TO SUBMIT DOCUMENTATION TO VERIFY ACCURACY OF FIELD ENGINEERING WORK SHOULD IT BE REQUESTED. ON COMPLETION OF THE PROJECT A CERTIFICATE IS TO BE SUBMITTED BY THE SURVEYOR TO CERTIFY THAT ELEVATIONS AND LOCATIONS OF COMPLETED WORK ARE IN CONFORMANCE OR NON-CONFORMANCE WITH THE CONSTRUCTION DRAWINGS AND SPECIFICATIONS. IN AREAS OF NON-CONFORMANCE THIS CERTIFICATE IS TO IDENTIFY THE AREAS AND REASONS FOR NON-CONFORMANCE.
- 13. NO DESIGN MODIFICATIONS SHALL BE MADE WITHOUT THE APPROVAL OF THE CONTRACT
- 14. IN ALL CASES WHERE A CONFLICT MAY OCCUR, SUCH AS BETWEEN ITEMS COVERED IN SPECIFICATIONS AND NOTES ON THE DRAWINGS. OR BETWEEN GENERAL NOTES AND SPECIFIC DETAILS, THE PROJECT CONTRACT ADMINISTRATOR SHALL BE NOTIFIED, AND THEY WILL INTERPRET THE INTENT OF THE CONTRACT DOCUMENTS. NO PART OF THE CONTRACT DOCUMENTS IS INTENDED TO BE IN VIOLATION OF CODES. IF DISCREPANCIES EXIST, CONTRACTOR TO NOTIFY CONTRACT ADMINISTRATOR IMMEDIATELY.
- 15. CONTRACTOR IS TO MAINTAIN PUBLIC ACCESS TO ALL DRIVEWAYS THROUGHOUT CONSTRUCTION.
- 16. THE CONTRACTOR IS TO RE-USE APPROVED EXCAVATED TOPSOIL, GRAVEL, COBBLE AND BOULDER MATERIAL WITHIN THE SITE. ALL RE-USED MATERIAL MUST BE REVIEWED AND APPROVED BY THE CONTRACT ADMINISTRATOR.

# ENVIRONMENTAL NOTES

- 1. REFER TO THE CONSTRUCTION ENVIRONMENTAL MANAGEMENT PLAN (CEMP) FOR ENVIRONMENTAL MANAGEMENT REQUIREMENTS.
- 2. ADVISE THE ENVIRONMENTAL MONITOR FOR ADDITIONAL MITIGATIONS REQUIRED IN THE EVENT THAT UNFORSEEN ENVIRONMENTAL RISKS ARISE.

PROTECTION OF EXISTING STRUCTURES NOTES THESE NOTES ADDRESS RESPONSIBILITIES OF THE CONTRACTOR TO PROTECT EXISTING STRUCTURES, INCLUDING, BUT NOT LIMITED TO:

- WALKWAYS, ROADS AND PARKING AREAS WITHIN POLSON PARK
- HWY 97 CULVERT CROSSING 900ø CONCRETE STORM OUTFALL
- 1. IT IS RECOMMENDED THAT WHILE CONDUCTING RECONSTRUCTION WORK WITHIN 5m OF ALL STRUCTURES, THE CONTRACTOR SHOULD COMPLETE A CRACK AND DAMAGE SURVEY WHICH WOULD CONSIST OF TWO PARTS. THE FIRST PART PRIOR TO CONDUCTING ANY RECONSTRUCTION ACTIVITIES SHALL INCLUDE A VISUAL INSPECTION, PHOTOGRAPHS, AND A WRITTEN REPORT DESCRIBING ANY EXISTING DEFECTS. THE SECOND PART WILL BE PERFORMED AFTER THE RESTORATION WORK IS COMPLETE AND SHALL ALSO INCLUDE A VISUAL INSPECTION, PHOTOGRAPHS, AND WRITTEN REPORT DESCRIBING ANY CHANGE IN THE STRUCTURE CONDITION. THE CONTRACT ADMINISTRATOR WILL COMPLETE A SIMILAR REVIEW ON BEHALF OF THE OWNER.
- 2. PRIOR TO STARTING CONSTRUCTION, CONTROL POINTS ARE TO BE ESTABLISHED ON THE STRUCTURES. THE CONTRACTOR SHALL ENGAGE THEIR SURVEYOR TO CONDUCT A BASELINE ELEVATION SURVEY OF ALL STRUCTURES AND COMPLETE REGULAR SURVEY READINGS TO DETERMINE IF ANY SETTLEMENT OR MOVEMENT IS OBSERVED AT THE STRUCTURES. IF CHANGES ARE OBSERVED, STOP CONSTRUCTION AND CONSIDER IMPLEMENTING ALTERNATE CONSTRUCTION METHODS.
- 3. CONTRACTOR TO COORDINATE CLOSURE OF BRIDGE AND WALKWAY STRUCTURES WITH THE CITY OF VERNON WHEN WORK IS BEING COMPLETED IN THEIR VICINITY.
- 4. THE CONTRACTOR IS RESPONSIBLE FOR ALL SHORING AND UNDERPINNING TO PREVENT DISTURBANCE TO THE STRUCTURES, AS REQUIRED. RETAIN A PROFESSIONAL ENGINEER REGISTERED IN THE PROVINCE OF BRITISH COLUMBIA TO COMPLETE ALL SHORING DESIGN WORK

5. PROVIDE CUTS IN THE EXISTING CONCRETE EMBANKMENT STABILIZATION AS OUTLINED IN THE PROJECT DOCUMENTS. CONTRACTOR SHALL NOT IMPACT OR UNDERMINE CONCRETE EMBANKMENT STABILIZATION ADJACENT TO STRUCTURE FOOTINGS WHEN REMOVING OTHER SECTIONS.

# TREE PROTECTION NOTES

1. ALL EXISTING TREES ARE TO REMAIN UNLESS OTHERWISE SHOWN ON THE DRAWINGS OR DIRECTED BY CONTRACT ADMINISTRATOR.

# TREE PROTECTION FENCING

SATISFACTION OF THE CONTRACT ADMINISTRATOR.

- 2. TREE PROTECTION FENCING MAY BE REQUIRED FOR ALL TREES AND/OR SIGNIFICANT STANDS OF EXISTING TREES WITHIN 6.0m OR LESS FROM THE LIMITS OF
- 3. PROTECTIVE FENCE IS TO BE INSTALLED PRIOR TO DEMOLITION OR OTHER SITE WORK AND MAINTAINED THROUGHOUT CONSTRUCTION UNTIL LANDSCAPE CONSTRUCTION IS
- 4. IF REQUIRED, TREES ARE TO BE PROTECTED WITH TEMPORARY FENCING CONSISTING OF 1.5m HIGH ORANGE PLASTIC CONSTRUCTION FENCE MOUNTED ON STEEL 'T'-BARS © 1.5m O.C. DRIVEN INTO GROUND A MINIMUM OF 0.6m. THE TREE PROTECTION ZONE (TPZ) WILL BE A MINIMUM DISTANCE OF 4.0m FROM THE TRUNK OF THE TREE OR TO THE DRIPLINE, WHICHEVER IS GREATER. THE CANOPY OF THE TREE SHALL BE PROTECTED TO THE DRIPLINE.

# TREE PROTECTION ZONE (TPZ)

- 5. TREE PROTECTION ZONES (TPZ) WILL BE IDENTIFIED BY CONTRACTOR AND VERIFIED IN FIELD BY PROJECT ENGINEER AND FENCED.
- 6. AREAS WITHIN THE DRIPLINE OF THE TREES ARE NOT TO BE USED FOR ANY TYPE OF STORAGE (E.G. STORAGE OF DEBRIS, SURPLUS SOILS). THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PROTECT PLANT AND ROOT SYSTEMS FROM DAMAGE,
  - DO NOT STORE EQUIPMENT OR CONSTRUCTION MATERIALS WITHIN THE TPZ.

COMPACTION AND CONTAMINATION RESULTING FROM THE CONSTRUCTION TO THE

- DO NOT STORE SOIL, CONSTRUCTION WASTE, OR DEBRIS WITHIN THE TPZ. DO NOT PERMIT VEHICLE, EQUIPMENT, OR PEDESTRIAN ACCESS THROUGH THE TPZ. UNLESS EXPRESSLY PERMITTED FOR THE MAINTENANCE OF THE TREES WITHIN THE AREA.
- DO NOT ALTER OR DISTURB THE GRADE WITHIN THE TPZ.

DO NOT DISPOSE OF LIQUIDS WITHIN THE TPZ.

- DO NOT PERFORM TRENCHING OR TUNNELING WITHIN THE DRIPLINE OF TREES. DESIGNATED FOR PROTECTION, UNLESS OTHERWISE SPECIFIED OR APPROVED BY THE CONTRACT ADMINISTRATOR
- DO NOT ATTACH OR WRAP ANY RIGGING CABLES OR HARDWARE OF ANY KIND AROUND PROTECTED TREES, WITHOUT APPROVAL FROM CONTRACT ADMINISTRATOR.
- ALL SUPPORTS AND BRACING FOR PROTECTIVE FENCING IS TO BE INSTALLED OUTSIDE THE TPZ. ALL SUPPORTS AND BRACING SHALL MINIMIZE DAMAGE TO TREE ROOTS OUTSIDE OF THE TPZ.
- DO NOT DUMP ANY POTENTIAL CONTAMINANTS WITHIN THE TPZ OR WHERE THEY MAY ENCOUNTER THE FEEDER ROOTS OF THE TREES.
- 7. IF PROTECTION TO THE EDGE OF DRIPLINE IS NOT FEASIBLE TREE PROTECTION MEASURES TO BE REVIEWED ON SITE WITH THE CONTRACT ADMINISTRATOR. AT MINIMUM FENCING TO BE INSTALLED 2.0m FROM TREE TRUNK.
- 8. PROTECTIVE BARRIER FENCING WILL REMAIN STANDING AND IN GOOD CONDITION UNTIL CONSTRUCTION COMPLETION.
- THE CONTRACTOR SHALL TAKE EVERY PRECAUTION TO PROTECT PLANT AND ROOT SYSTEMS FROM DAMAGE, COMPACTION AND CONTAMINATION RESULTING FROM THE CONSTRUCTION TO THE SATISFACTION OF THE CONTRACT ADMINISTRATOR.

# PRUNING OF PROTECTED TREES

- 10. IN THE EVENT THAT IT IS NECESSARY TO REMOVE LIMBS OR PORTIONS OF TREES TO ACCOMMODATE CONSTRUCTION, CONTRACT ADMINISTRATOR IS TO BE INFORMED AND THE REMOVAL IS TO BE EXECUTED CAREFULLY AND IN ACCORDANCE WITH PROPER ARBORICULTURAL TECHNIQUES BY A CERTIFIED ARBORIST. ON-SITE APPROVAL BY PROJECT ENGINEER IS REQUIRED PRIOR TO REMOVAL OPERATIONS.
- 11. DURING EXCAVATION OPERATIONS IN WHICH ROOTS ARE AFFECTED, THE CONTRACTOR IS TO PRUNE ALL EXPOSED ROOTS CLEANLY. PRUNED ENDS TO POINTED OBLIQUELY DOWNWARDS. DO NOT ALLOW EXPOSED ROOTS TO DRY OUT. THE CONTRACTOR SHALL DISCUSS WATERING OF THE ROOTS WITH THE CONTRACT ADMINISTRATOR SO THAT OPTIMUM SOIL MOISTURE IS MAINTAINED DURING CONSTRUCTION AND BACK FILLING OPERATIONS, SO AS NOT TO INTERFERE WITH CONSTRUCTION OPERATIONS.

# COMMUNICATION PLAN

- 12. THE CONTRACTOR IS TO IMPLEMENT A COMMUNICATION PLAN TO ENSURE TREE PROTECTION REQUIREMENTS ARE FOLLOWED.
- 13. THE CONTRACT ADMINISTRATOR WILL OVERSEE TREE PROTECTION REQUIREMENTS. THE CONTRACT ADMINISTRATOR WILL BE PROVIDED CONTACT INFORMATION FOR THE SITE SUPERVISOR AND ALL REPLACEMENTS SHOULD THE MAIN SITE SUPERVISOR NOT BE
- 14. FOR ALL TREE RELATED ISSUES THE CONTRACT ADMINISTRATOR WILL BE NOTIFIED IMMEDIATELY TO DISCUSS THE ISSUES AND REQUIRED MITIGATION.
- 15. THE CONTRACTOR IS TO MONITOR TREE CONDITION DURING CONSTRUCTION. ENSURE
- TREES ARE NOT DAMAGED OR SHOWING SIGNS OF DECLINE. 16. IF GRADES WITHIN THE DRIPLINE OF AN EXISTING TREE ARE TO BE CHANGED REFER TO GRADING NOTES.

# CREEK DIVERSION NOTES

- CONTRACTOR IS RESPONSIBLE FOR THE SUPPLY, INSTALLATION, MAINTENANCE AND MODIFICATION OF THE ISOLATION AND CREEK DIVERSION MEASURE REQUIRED TO
- FACILITATE CONSTRUCTION. 2. THE CITY HAS IDENTIFIED TWO FEASIBLE OPTIONS FOR CREEK DIVERSION.
- 2.1. DAM THE CREEK IMMEDIATELY UPSTREAM OF THE WORKS AND INSTALL A GRAVITY DIVERSION CONSISTING OF PIPE AND LINED CHANNEL, THROUGH THE WORK AREA TO THE DOWNSTREAM END OF THE WORK AREA.
- DAM THE CREEK IMMEDIATELY UPSTREAM OF THE WORKS, INSTALL PUMPS TO DRAW THE WATER ABOVE THE CHANNEL BANK TO CARRY DIVERTED WATER PAST THE WORK AREA AND RELEASE IT DOWNSTREAM OF THE WORK AREA. 3. HISTORICALLY, THE MEAN PEAK CREEK DISCHARGE IN AUGUST IS 0.93 m<sup>3</sup>/s. THE
- HISTORIC 10-YEAR AUGUST FLOW IS 2.17 m<sup>3</sup>/s. 4. THE CONTRACTOR IS RESPONSIBLE FOR THE SIZING OF THE PUMPS, PIPES, DIVERSION DAMS AND RELATED COMPONENTS REQUIRED TO FACILITATE THE WORKS.
- 5. CREEK ISOLATION AND DIVERSION MEASURES TO BE EXECUTED IN ACCORDANCE WITH THE REGULATORY APPROVALS. 6. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLING FLOW DISPERSION FEATURES AT
- THE OUTLET TO ENSURE THAT THE VELOCITY OF THE DIVERTED FLOW DOES NOT CREATE EROSION, DAMAGE THE RESTORED CREEK, OR DAMAGE DOWNSTREAM INFRASTRUCTURE
- ALL PIPE MUST BE PRESSURE-WASHED TO REMOVE ALL DUST AND DEBRIS PRIOR BEING DELIVERED TO THE SITE.
- 8. ALL DIVERSION PIPE MUST BE SUPPORTED DURING CONSTRUCTION IN ORDER TO ENSURE ITS INTEGRITY WITH EXTRA CARE TAKEN AT EQUIPMENT CROSSING LOCATIONS.
- 9. A DIVERSION ROUTE SHALL BE DETERMINED BY THE CONTRACTOR TO MAXIMIZE THE EFFICIENCY OF THE PROJECT WHILE ADHERING TO THE SPECIFICATIONS DEFINED HEREIN WITH REGARDS TO SAFETY, TRAFFIC AND EXISTING INFRASTRUCTURE.

### 10. THE CONTRACTOR IS RESPONSIBLE FOR MONITORING CREEK FLOWS UPSTREAM OF THE SITE. IF THE IMPOUNDED DEPTH OF WATER MEETS OR EXCEEDS 1.2m, CONTRACTOR IS TO NOTIFY THE CONTRACT ADMINISTRATOR AND TAKE MEASURES TO ENSURE THE SAFETY OF THE SITE AND CONSTRUCTION AREA

11. CONTRACTOR IS TO MONITOR THE INLET OF THE DIVERSION SYSTEM FOR DEBRIS AND BLOCKAGES ON A REGULAR BASIS. ANY DEBRIS OR BLOCKAGES ARE TO BE CLEARED.

# GRADING NOTES

- 1. ESTABLISH POSITIVE DRAINAGE THROUGHOUT THE SITE.
- 2. REHABILITATED SOFT LANDSCAPE AREAS SHALL HAVE A GRADIENT NO LESS THAN 2.0% AND NO MORE THAN 33% - UNLESS OTHERWISE NOTED ON DRAWINGS
- IF GRADES WITHIN THE DRIPLINE OF AN EXISTING TREE ARE TO BE CHANGED, THE CONTRACTOR SHALL BE REQUIRED TO CONTACT THE CONTRACT ADMINISTRATOR PRIOR TO GRADING WITHIN THE DRIPLINE SO THAT PRECAUTIONS TO PRESERVE THE TREE CAN BE DETERMINED.
- 4. PRIOR TO SITE GRADING REVIEW ON SITE WITH THE CONTRACT ADMINISTRATOR, THE IMPACT OF GRADING AROUND EXISTING TREES TO REMAIN.
- FIELD FIT GRADING ADJACENT TO EXISTING TREES TO PRESERVE AND MAINTAIN EXISTING GRADE MINIMUM 2.0m FROM TRUNK WHERE FEASIBLE.
- WHERE GRADING CHANGES WITHIN THE DRIPLINE, THE INTENT IS TO MAINTAIN THE TREE FOR FISH HABITAT ENHANCEMENTS. IF SITE WORKS EXPOSE ROOTS REFER TO TREE PROTECTION NOTES FOR ROOT PRUNING TECHNIQUES.
- DURING THE MAINTENANCE PERIOD IF STRUCTURAL INTEGRITY OF TREES WITH GRADING COMPLETED WITHIN THE DRIPLINE IS DEEMED UNSAFE BY A DANGER TREE ASSESSOR, THE TREE IS TO BE FELLED AND REMOVED FROM SITE BY A CERTIFIED PROFESSIONAL IN A MANNER TO ENHANCE FISH HABITAT.

# ROCK/MATERIAL PLACEMENT NOTES

- PLACE RIPRAP BEDDING, RIPRAP AND BOULDER AT THE LOCATIONS, AND TO THE LINES, GRADES, AND ELEVATION SPECIFIED IN THE DRAWINGS.
- RECEIVING SURFACES ARE TO CONSIST OF NATIVE GRAVELS. IF THIS IS NOT THE CASE, THE CONTRACTOR IS TO OVER-EXCAVATE 100mm AND PLACE 100mm OF GRAVEL INFILL MATERIAL BEFORE PLACING CHANNEL BED MATERIAL
- 3. CONCRETE AND OTHER DELETERIOUS MATERIALS MUST BE REMOVED FROM RECEIVING SURFACES.
- 4. DO NOT PLACE CHANNEL BED MATERIAL UNTIL THE RECEIVING SURFACES HAVE BEEN INSPECTED BY THE CONTRACT ADMINISTRATOR. RECTIFY DEFECTS UNTIL THE RECEIVING SURFACES MEET THE REQUIREMENTS OF THE CONTRACT
- PLACE BY BACKHOE WITH A THUMB, OR SIMILAR LIFTING EQUIPMENT. DO NOT END DUMP AND PUSH CHANNEL BED MATERIAL INTO PLACE ON THE SLOPES.
- DO NOT CAUSE SEGREGATION, PARTICLE DAMAGE, BREAKDOWN, OR EXCESSIVE DISPLACEMENT OF THE PREVIOUSLY PLACED CHANNEL BED MATERIAL. REPLACE OR REPAIR DAMAGED OR DISPLACED MATERIAL.
- OBTAIN THE SPECIFIED DISTRIBUTION OF THE VARIOUS SIZES OF PARTICLES THROUGHOUT BY USING SELECTIVE LOADING AT THE SOURCE OR STOCKPILE
- 8. COMMENCE PLACEMENT OF CHANNEL BED MATERIAL FROM THE TOE OF THE SLOPE AND PROCEED UP THE SLOPE.
- 9. PLACE CHANNEL BED MATERIAL TO ITS FULL THICKNESS IN ONE OPERATION. COMPACTION IS NOT REQUIRED.
- 10. PLACE CHANNEL BED MATERIAL IN A CLOSELY PACKED ARRANGEMENT SUCH THAT SMALLER ROCKS FILL THE VOIDS BETWEEN LARGER ROCKS AND THERE ARE NO UNFILLED SPACES THAT WOULD PERMIT THE ESCAPE OF UNDERLYING LAYERS OF PLACED MATERIALS. INTERLOCK PARTICLE AND DRESS SLOPES AS REQUIRED.
- 11. REARRANGE ROCKS TO ELIMINATE ANY TENDENCY OF THE ROCKS TO MOVE OR SLIDE AFTER PLACEMENT.
- 12. DO NOT BREAK INDIVIDUAL CHANNEL BED MATERIAL PARTICLES AFTER PLACEMENT. 13. FILL THE CHANNEL BED MATERIAL VOIDS WITH GRAVEL INFILL MATERIAL OR TOPSOIL IN
- 14. PLACE LARGE AND SMALL SPAWNING GRAVELS AS SPECIFIED ON THE DRAWINGS 15. PROVIDE A COMPLETED CHANNEL BED MATERIAL SURFACE THAT IS SMOOTH, REGULAR,
- UNIFORM WITH SOME EMERGENT BOULDERS AS DIRECTED BY THE CONTRACT
- 16. ALL LOGS PLACED IN THE CHANNEL ARE TO BE UNTREATED.

AREAS WHERE SPECIFIED IN THE CONTRACT.

# GRAVEL INFILL MATERIAL WASHING NOTES

- GRAVEL IN VOIDS IS TO BE INSTALLED IN 50mm LIFTS WITH EACH LIFT BEING "WASHED" IN TO FILL THE VOIDS BETWEEN THE ROCKS.
- 2. REFER TO WATER SUPPLY NOTES FOR WASH WATER SOURCE WITH BEST PRACTICES BEING UTILIZED (e.g. FISH SCREEN ON INTAKE, REMOVAL DEBRIS FROM SCREEN, ETC.).
- 3. CONTRACTOR TO ENSURE THAT THE WASHING PROCESS DOES NOT GENERATE RUNOFF THAT IMPACTS THE CREEK OUTSIDE THE WORK AREA. 4. SEDIMENT-LADEN WATER MUST NOT BE RELEASED OUTSIDE THE WORK AREA. PUMPING OF SEDIMENT LADEN WATER AND REMOVAL FROM SITE VIA TANKER TRUCK MAY BE
- REQUIRED. REFER TO ESC MEASURES OUTLINED IN THE CEMP. 5. ONCE VOIDS HAVE BEEN FILLED. CONTRACTOR IS TO TEST THE VOIDS BY ADDING WATER ATOP THE FINISHED SURFACE. AREAS WHERE WATER FLOWS ON THE SURFACE AND NOT SEEP THROUGH THE VOIDS IN THE ROCKS WILL BE CONSIDERED TO HAVE ADEQUATE VOIDS FILLED. AREAS WHERE WATER FLOW ENTERS THE ROCK VOIDS ARE TO BE INFILLED WITH ADDITIONAL GRAVEL AND RETESTED. THE PROJECT ENGINEER SHALL BE IN ATTENDANCE FOR THESE TESTS AND SHALL PROVIDE APPROVAL OF

# WATER SUPPLY NOTES

- 1. THE CONTRACTOR IS RESPONSIBLE TO PROVIDE THE NECESSARY WATER REQUIRED TO MEET THE MOISTURE CONDITIONS OF ALL BACKFILL MATERIALS, LANDSCAPING AND PROVIDE DUST CONTROLS AT ALL TIMES.
- 2. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO ADHERE TO THE CURRENT POLICIES SET FORTH BY THE PROVINCE WITH RESPECT OF WITHDRAWAL FROM WATER
- 3. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING WATER TO MEET THE PROJECT REQUIREMENTS, ANY ASSOCIATED COSTS, PERMITS OR APPROVALS IS CONSIDERED INCIDENTAL TO THE CONTRACT.

# MATERIAL SIZING

# **BOULDER CLUSTER MATERIAL**

100 450 0 400	PERCENT FINER	GRAIN SIZE (mm)
0 400	100	450
	0	400

PERCENT FINER	GRAIN SIZE (mm)
100	450
0	400

# **ROCK LINES**

PERCENT FINER	GRAIN SIZE (mm)
100	715
0	600

# CHANNEL BED / COBBLE BOULDER MATERIAL

PERCENT FINER	GRAIN SIZE (mm)
100	450
85	380
50	260
15	120

# GRAVEL INFILL MATERIAL

PERCENT FINER	GRAIN SIZE (mm)
100	152
85	102
50	76
25	25
15	13
5	2
0	0.0625

# SMALL SPAWNING GRAVE

PERCENT FINER	GRAIN SIZE (mm)
100	75
75	50
0	19

# LARGE SPAWNING GRAVE

THE STATES STATES	
PERCENT FINER	GRAIN SIZE (mm)
100	100
75	75
0	50

# CLASS 50 KG RIPRAF


2.00 00 1.0 1.11 1.11	
PERCENT FINER	GRAIN SIZE (mm)
100	565
85	475
50	330
15	155

# CLASS 250 KG RIPPAP

ASS 250 KG RIPKAP	
PERCENT FINER	GRAIN SIZE (mm)
100	965
85	815
50	565
15	260

 FIR LOG WITH ROOT ATTACHED, 5m LONG, DIAMETER 250-350mm. ROOT WAD MINIMUM OF 800mm DIAMETER.

- FIR LOG WITHOUT ROOT OR BRANCHES ATTACHED, 10m LONG, DIAMETER 250-350mm.












**SCALE** H: N/A **V:** N/A


GENERAL NOTES & MATERIAL SIZING


SHEET POLSON PARK NATURALIZATION PHASE 2 4 OF

















29.01.2	ğ	188UE No.	DATE	DESIGNED	DRAWN	CHECKED	DESCRIPTION	
12		0	24/01/29	IB	JI	LB	ISSUED FOR PROPOSAL	
	2							<b>/</b>
	3							
								$\dashv$ \
	E/F							
	3							










<b>9CALE H:</b> 1:250 <b>V:</b> 1:50	
SHEET	


11 **OF** 


CHANNEL PLAN/PROFILE
REACH 2 DOWNSTREAM CHANNEL TIE—IN
POLSON PARK NATURALIZATION
PHASE 2




















B TWO RAIL SPLIT TIMBER FENCE
C225-C227 1:50








<b>8CALE H:</b> 1:250 <b>V:</b> 1:50	
SHEET	


16 **o**F

MULTI-USE PATHWAY PLAN/PROFILE
STA 1+290 - 1+345
POLSON PARK NATURALIZATION
PHASE 2

**DRAWING NUMBER**C227

29.01.2024















ENGINEERING AND GIS SERVICES


POLSON PARK NATURALIZATION PHASE 2




























ORIGINAL GROUND FINISHED GROUND

| Seven No. | Date | Designed | Drawn | Checked | Designed | Drawn | Checked | Designed | Drawn | Checked | Designed | Drawn | Description | D









**9CALE H:** 1:250 **V:** 1:125


SECTIONS


SHEET
17 OF

POLSON PARK NATURALIZATION PHASE 2










ORIGINAL GROUND -----FINISHED GROUND

2	ISSUE No.	DATE	<b>DESIGNED</b>	DRAWN	CHECKED	DESCRIPTION
	0	24/01/29	IB	J	LB	ISSUED FOR PROPOSAL
12						
18						
12						
1						
I						
I -						







SCALE
H: 1:250 V: 1:125


TITLE SECTIONS


**SHEET**18 **OF** 


POLSON PARK NATURALIZATION PHASE 2


DRAWING NUMBER
C311


\\CA0047-PPFSS01\WORKGROUP\01117\active\111710119\4\_
























ORIGINAL GROUND -----FINISHED GROUND —

NO.	ISSUE No.	DATE	<b>DESIGNED</b>	DRAWN	CHECKED	DESCRIPTION
1	0	24/01/29	IB	JI	LB	ISSUED FOR PROPOSAL
2			_			
			_			
8						











SECTIONS


**SHEET**19 **OF** 


POLSON PARK NATURALIZATION PHASE 2




















ORIGINAL GROUND -----FINISHED GROUND

	<b>188UE No.</b>	DATE	DESIGNED	DRAWN	CHECKED	DESCRIPTION
	0	24/01/29	IB	J	LB	ISSUED FOR PROPOSAL
2						
18						
12						
13						
- 1						









SCALE	
<b>H:</b> 1:250 <b>V:</b> 1:125	
	١


TITLE SECTIONS


**SHEET**20 **o**F


POLSON PARK NATURALIZATION PHASE 2





















ORIGINAL GROUND -----FINISHED GROUND

ISSUE No.	DATE	<b>DESIGNED</b>	DRAWN	CHECKED	DESCRIPTION
0	24/01/29	IB	JI	LB	ISSUED FOR PROPOSAL
		_			
•					O 24/01/29 IB JI LB









<b>9CALE H:</b> 1:250 <b>V:</b> 1:125
<b>V:</b> 1:125

SECTIONS


**SHEET**21 **o**F

POLSON PARK NATURALIZATION PHASE 2











NOTES:

1. SUPPLY AND INSTALL 12mmØ 150mm
HILTI-KNIT BOLT (MINIMUM 100mm
EMBEDMENT) c/w HILTI HIT-RE 500 V3 SYSTEM
INTO ANCHOR BOULDERS IN ACCORDANCE
WITH THE MANUFACTURER'S INSTRUCTIONS.


4 TYPICAL LOG ANCHOR DETAIL
C502 NTS




# SECTION - RIFFLE POOL w/ RIPRAP AND BRUSH BANK



# SECTION - RIFFLE POOL w/ RIPRAP AND COBBLE BOULDER BANK



SECTION - RIFFLE POOL w/ LOG BANK



TYPICAL BANK TREATMENT DETAILS

NTS

Į	ISSUE No.	DATE	DESIGNED	DRAWN	CHECKED	DESCRIPTION
≨	0	24/01/29	IB	JI	LB	ISSUED FOR PROPOSAL
12						
Z						
▮						
lì						







SCALE H: N/A V: N/A
SHEET


TYPICAL CHANNEL DETAILS

9HEET F

POLSON PARK NATURALIZATION PHASE 2

<u>PLAN VIEW</u>





# NOTES:

- 1. BOULDERS FOR THE ROCK LINE MUST HAVE A HAVE A DIAMETER OF 400-450mm.
- HEADER BOULDERS SHALL BE UNDERLAIN BY FOOTER BOULDERS UNLESS OTHERWISE DIRECTED BY THE QUALIFIED PROFESSIONAL. FOOTER BOULDERS SHALL BE INSTALLED FIRST AND POSITIONED TO SUPPORT HEADER BOULDERS ABOVE. HEADER BOULDERS SHALL BE OFFSET SLIGHTLY UPSTREAM OF THE FOOTER BOULDERS.
- 3. SET INVERTS AT ELEVATION SHOWN ON THE PLAN AND PROFILE SHEETS WITH NO DROP IN ELEVATION ACROSS EACH LINE.
- 4. THE ROCK LINE SHALL BE PLACED PERPENDICULAR TO THE CHANNEL BANKS. LOCATION OF ALL ROCK LINES SHOWN ON THE PLAN AND PROFILE SHEETS (C201 TO C203).
- 5. THE VERTICAL SLOPE OF EACH ROCK LINE SHALL NOT EXCEED 10% UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- 6. ALL GAPS/VOIDS LARGER THAN 50 mm BETWEEN THE HEADER AND FOOTER BOULDERS SHALL BE HAND CHINKED WITH COBBLE AND GRAVEL ON THE UPSTREAM SIDE WITH GRAVEL INFILL MATERIAL. ALL CHINKING SHALL BE APPROVED BY THE QUALIFIED PROFESSIONAL BEFORE THEY ARE BACKFILLED.
- 7. BACKFILL BETWEEN LINES WITH COBBLE BOULDER MATERIAL (SEE G004).
- 8. INFILL BED WITH GRAVEL INFILL MATERIAL. USE A PUMP AND HOSE TO WASH THE GRAVEL INFILL MATERIAL INTO VOIDS SUCH THAT WATER FLOWS OVER THE BED AND NOT THROUGH IT. INFILLING SHALL BE APPROVED BY THE QUALIFIED PROFESSIONAL.
- 9. SELECT BACKFILL AND SOIL BACKFILL MATERIAL ON THE BANKS SHALL BE COMPACTED SUCH THAT FUTURE SETTLEMENT OF THE MATERIAL IS KEPT TO A MINIMUM.
- 10. THE SURFACE OF THIS STRUCTURE SHALL BE FINISHED TO A ROUGH IRREGULAR SURFACE IN ACCORDANCE WITH THE LINES, GRADES, AND CROSS-SECTIONS OR ELEVATIONS SHOWN ON THE DRAWINGS. THE DEGREE OF FINISH FOR INVERT ELEVATIONS SHALL BE WITHIN 30 mm OF THE GRADES AND ELEVATIONS INDICATED, PROVIDED ANY HEIGHT DOES NOT EXCEED MAX. ALLOWABLE DROP OF 120mm FOR THIS STRUCTURE.

# NOTES:

- 1. BOULDERS FOR THE CLUSTERS SHALL HAVE A DIAMETER OF 600-715mm.
- 2. BOULDER CLUSTERS SHALL BE INSTALLED UNDER THE DIRECT SUPERVISION OF THE QUALIFIED PROFESSIONAL. BOULDER CLUSTERS ARE TO BE INSTALLED WITHIN THE CHANNEL DURING LOW FLOW (WITH FISH ISOLATION) TO ADJUST PLACEMENT AS REQUIRED FOR THE FLOW CONDITIONS.
- 3. BOULDERS SHALL BE PLACED IN GROUPS OF THREE, WITHIN THE MIDDLE 3/4 OF THE CREEK, IN PATTERNS THAT DO NOT DIRECT FLOW TOWARDS THE BANKS.
- 4. BOULDERS SHALL PROTRUDE 200-300mm ABOVE THE CHANNEL BED.
- 5. SPACE THE BOULDERS AS SPECIFIED IN THE DETAIL ENSURING THAT NO MORE THAN 20% OF THE STREAM WIDTH IS OBSTRUCTED AT ANY GIVEN POINT.

6 BOULDER CLUSTER DETAIL
C503 NTS

	ISSUE No.	DATE	<b>DESIGNED</b>	DRAWN	CHECKED	DESCRIPTION
	0	24/01/29	IB	JI	LB	ISSUED FOR PROPOSAL
Š						
2						








**8CALE** H: N/A V: N/A


SCALE
1: N/A
1: N/A
1: N/A
1: N/A
1: N/A

SHEET


21 **OF** 

POLSON PARK NATURALIZATION PHASE 2





# SECTION B-B CASCADE



# SECTION C-C DEEP POOL

# NOTES:

- 1. EXCAVATE TO SUBGRADE SURFACE
- 2. INSTALL ROOTWADS IN TRENCH AT 5% SLOPE TOWARDS THE CHANNEL WITH THE
- ROOTWAD 1m INTO THE CHANNEL FROM THE BANK
- 3. ANCHOR ROOTWADS AS PER TYPICAL LOG ANCHOR DETAIL 4. PLACE CLASS 250 KG RIPRAP BALLAST OVER LOGS
- 5. FORM BANKS FROM CLASS 250 KG RIPRAP
- 6. BACKFILL TRENCH WITH SELECT INFILL MATERIAL
- INSTALL ROCK LINE, KEYSTONES AND CASCADE INTO THE DEEP POOL 8. PLACE CHANNEL BED MATERIAL AND WASH IN GRAVEL INFILL MATERIAL
- 9. PLACE LARGE SPAWNING GRAVELS AS PER TYPICAL DETAIL
- 10. ENSURE POOL IS NOT INFILLED BEYOND DESIGNED POOL DEPTH

7	DEEP	POOL	DETAIL
C504	NTS		

ğ	188UE No.	DATE	DESIGNED	DRAWN	CHECKED	DESCRIPTION
≨	0	24/01/29	IB	JI	LB	ISSUED FOR PROPOSAL
💆						
18						
=						
1 🗮						









<b>9CALE</b> H: N/A V: N/A
SHEET

22 **OF** 

TYPICAL CHANNEL DETAILS

POLSON PARK NATURALIZATION PHASE 2





**TYPICAL** ON-CENTER SIZE **FORM** SCIENTIFIC NAME PLANTING ZONE COMMON NAME QUANTITY SPACING (m) Populus trichocarpa Trees black cottonwood live-stake 63 Flood Fringe red-twig dogwood 562 Cornus sericea live-stake Shrubs Salix drummondiana Drummond's willow 422 live-stake Populus trichocarpa 1.5m height black cottonwood hybrid white x Engelmann spruce Picea engelmannii x glauca 1.5m height 1.5m height Pinus ponderosa Ponderosa pine 3 36 Trees 1.5m height Pseudotsuga menziesii interior Douglas-fir 59 Populus tremuloides 1.5m height 23 quaking aspen Cornus sericea red-osier dogwood #2 pot 198 Symphoricarpos albus common snowberry 2 #1 pot 133 Mid-bench / Douglas maple Acer glabrum 2 #2 pot 151 Upland Nootka rose #1 pot 208 Rosa nutkana Saskatoon berry Amelanchier alnifolia #2 pot 163 Shrubs black gooseberry 2 Ribes lacustre #1 pot 197 Salix bebbiana Bebb's Willow 2 #1 pot 224 Mahonia aquifolium tall Oregon-grape #1 pot 196 Philadelphus lewisii Lewis's mock orange 2 #1 pot 125 Prunus virginiana Chokecherry 2 #1 pot 56

\* TYPICAL ON-CENTER SPACING - REFER TO LANDSCAPE DRAWINGS

# FLOOD FRINGE / MID-BENCH RECLAMATION SEED MIX

COMMON NAME	SCIENTIFIC NAME	PERCENT BY WEIGHT
Spike bentgrass	Agrostis exerata	20
California oatgrass	Danthonia californica	5
Tufted harigrass	Deschampsia cespitosa	5
Blue wildrye	Elymus glaucus	15
Slender wheatgrass	Elymus trachycaulus	20
Western wheatgrass	Pascoyrum smithii	20
Fowl bluegrass	Poa palustris	15

# <u>UPLAND RECLAMATION SEED MIX</u>

COMMON NAME	SCIENTIFIC NAME	PERCENT BY WEIGHT
Spike bentgrass	Agrostis exerata	10
Blue wildrye	Elymus glaucus	10
Slender wheatgrass	Elymus trachycaulus	10
Idaho fescue	Festuca idahoensis	20
Prairie junegrass	Koeleria macrantha	20
Western wheatgrass	Pascoyrum smithii	10
Bluebunch wheatgrass	Pseudoroegneria spicata	20

# TYPICAL PLANTING ARRANGEMENT - PLAN

5 | ISSUE No. | DATE | DESIGNED | DRAWN | CHECKED | DESCRIPTION ISSUED FOR PROPOSAL |24/01/29| IB 0

4. PLANT STOCK SHOULD BE INSPECTED BY A DESIGN ECOLOGIST PRIOR TO COMMENCING PLANTING WORKS.

SPECIES, PROPORTIONS, OR LAYOUTS MUST BE APPROVED BY THE DESIGN ECOLOGIST PRIOR TO IMPLEMENTING CHANGES.







SCALE
H: – V: –

PLANTING DETAILS

SHEET

POLSON PARK NATURALIZATION PHASE 2

DRAWING NUMBER

C611

27 **OF** 

5 SUB-SOIL

8 USE THREE 1800mm PAINTED T-BARS





**SCALE** H: – V: –

TITLE PLANTING DETAILS

SHEET


POLSON PARK NATURALIZATION

MID-BENCH TRANSITIONAL FLOOD FRINGE UPLAND (WIDTH VARIES) (WIDTH VARIES) MID-BENCH (2.6m) PLACE AMENDED TOPSOIL AND GRAVELS ~ ON TOP OF FINISHED GRADE (TYP) PLACE 450mm OF AMENDED TOPSOIL ON -/ MID-BENCH AND UPLAND REGIONS (TYP) PLACE 100-350mm OF AMENDED TOPSOIL AND 100mm OF LARGE SPAWNING GRAVEL ON TRANSITIONAL MID-BENCH REGIONS (TYP) PLACE 100mm LARGE SPAWNING GRAVEL -ON FLOOD FRINGE REGION (TYP)

TYPICAL TOPSOIL SECTION

# TYPICAL TOPSOIL PLACEMENT SECTION

SCALE: N.T.S.



STAKING PLAN: GUYING STAKING PLAN: T-BAR


# NOTES:

- TREES TO BE OVERSEEDED UNLESS OTHERWISE NOTED.PRUNE AWAY ANY GIRDLING ROOTS.
- PRUNE BROKEN AND FRAYED ROOT ENDS WITH SECATEURS. - HOLD TRUNK VERTICAL. BACKFILL AROUND ROOTS WITH TOPSOIL, CONTINUOUSLY PACKING THE SOIL UNTIL FIRM. DO NOT ALLOW AIR POCKETS TO FORM.
- TREE SHOULD BE PLANTED 75mm 100mm BELOW GROUND LEVEL. - IF TREE IS IN A WIRE BASKET, CUT AND REMOVE STRAPPING AND THE HORIZONTAL/VERTICAL WIRES OF THE UPPER 3 AS A MINIMUM. PULL BACK BURLAP TO THE SAME MINIMUM. - T-BARS SHOULD BE HAMMERED DOWN INTO SOLID FOOTING (MINIMUM
- 400mm INTO SUBSOIL). - STAKING TO BE IN PLACE FOR A MAXIMUM OF ONE YEAR, WHEN
- STAKE BEYOND EDGE OF ROOT BALL.
- USE RUBBER STRAPS (TO PROTECT THE TREE) AT POINT OF CONTACT
- PRUNE DEAD / DYING / DISEASED BRANCHES TO MAINTAIN NATURAL FORM OF TREÉ
- ALL DIMENSIONS IN mm.

# TYPICAL PLANTING DETAIL FOR 1.5m HEIGHT TREE SCALE: N.T.S.

TISH COLUMN	.• /
2863 2024	
Z Loy My Bu/go	
HAG.	• 7 7
OF AGROV	

















R-12T

R-12





DETAIL A CLASS 3 BARRICADE c/w TYPE A YELLOW FLASHERS (TYP.)

1-----CONSTRUCTION PHASE BOUNDARY


# GENERAL NOTES - TRAFFIC CONTROL

- 1. CONTRACTOR TO ISOLATE WORK AREA FROM PEDESTRIAN
- 2. CONTRACTOR TO MAINTAIN VEHICLE ACCESS AT PARK ENTRANCES AND EXITS AT ALL TIMES.

# TRAFFIC MANAGEMENT NOTES:

- 1. TRAFFIC MANAGEMENT SIGNAGE PLAN SHOWN IS AN EXAMPLE. CONTRACTOR TO USE AS REFERENCE FOR THEIR TRAFFIC MANAGEMENT PLAN.
- 2. ALL NOTICE OF CONSTRUCTION SIGNAGE SHALL BE IN PLACE FOR THE DURATION OF THE PROJECT.
- 3. ALL CONSTRUCTION SIGNAGE SHALL MOVE WITH THE WORK AREAS AS REQUIRED.
- 4. THE CONTRACTOR SHALL ERECT ALL SIGNAGE AND OBTAINED A PERMIT TO WORK WITHIN CITY RIGHT-OF-WAY PRIOR TO CONSTRUCTION.
- 5. THE CONTRACTOR SHALL CHECK FOR CONFLICTING INFORMATION ON EXISTING SIGNAGE AND ADVISE THE CONTRACT ADMINISTRATOR.
- 6. THE CONTRACTOR SHALL COORDINATE WITH AFFECTED BUSINESSES TO MAINTAIN VEHICLE ACCESS AS REQUIRED. MINIMUM SINGLE LANE ACCESS TO ALL DRIVEWAYS SHALL BE MAINTAINED FOR LOCAL TRAFIC.
- 7. SIGNAGE AND SPACING SHALL BE IN CONFORMANCE WITH THE BC MINISTRY OF TRANSPORTATION AND INFRASTRUCTURE'S TRAFFIC CONTROL MANUAL FOR WORK ON ROADWAYS (LATEST
- 8. SIGNAGE SHOWN REPRESENTS MINIMAL REQUIREMENTS. THE CONTRACTOR SHALL TAKE OWNERSHIP OF THE TRAFFIC MANAGEMENT PLAN AND MAKE MODIFICATIONS AS THE CONTRACTOR DEEMS NECESSARY WITH THE APPROVAL OF THE CONTRACT ADMINISTRATOR.
- 9. THE CONTRACTOR IS TO ENSURE ACCESS TO FIRE HYDRANTS AT
- ALL TIMES.
- 10. THE CONTRACTOR SHALL COORDINATE WITH EMERGENCY SERVICES WEEKLY FOR ACCESS TO THE AREA.
- 11. THE CONTRACTOR SHALL PROVIDE SAFE ACCESS FOR
- PEDESTRIANS OUTSIDE THE WORK AREA AT ALL TIMES. 12. THE CONTRACTOR SHALL SUPPLY CONTRACT ADMINISTRATOR WITH UPDATED TRAFFIC MANAGEMENT PLANS AS REQUIRED.

3210			PARK ENTRANC EXIT	2704	PARK ENTRANCE / EXIT O	2601	PLAN 62
3201		POLSON	PARK		Tho WAY TRAFFIC	2511	
3209 3207 3205		ONE WAY RAFFIC	Reserved to the second	2600		56064	PLAN 62138
2311 2310 AH	2311		CLASS 3 BARR TYPE A YELLOV SEE DETAIL A	CADE c/w V FLASHER,			
2303 2302 2301 2215 2214				TEMPOR FENCE (1	ARY CONSTRUCTION YP)		27.87
2208 2207 2206 2203						TE	MPORARY
2115 2114 2106	2101	VERNON JUBILEE HOSPITAL				ST	MPORARY OCKPILE LOCATION
2103						PEDESTRIAN TO BE MA ALONG F	ACCESS NTAINED ATHWAY
2008	2863 20 24 1	EPP35469	CITY OF	SCALE T	TRAFFIC MANAGEME	NT PLAN	1:1000 10 30 50m









ENGINEERING AND GIS SERVICES

**V:** N/A

26 **o**f

SHEET

POLSON PARK NATURALIZATION PHASE 2

DRAWING NUMBER

C702

- 1.2 SPECIFIC STRUCTURAL DRAWING NOTES SUPERSEDE GENERAL NOTES WHERE THEY ARE IN CONFLICT.
- 1.3 CONSTRUCTION OF THE WORKS SHALL COMPLY WITH MASTER MUNICIPAL CONSTRUCTION DOCUMENTS (MMCD) AND PROJECT SPECIFIC SUPPLEMENTARY SPECIFICATIONS.
- 1.4 THE CONTRACTOR SHALL EXAMINE ALL CONTRACT DOCUMENTS, CHECK DIMENSIONS AND REPORT ANY DISCREPANCIES TO THE CONTRACT ADMINISTRATOR FOR CLARIFICATION PRIOR TO COMMENCING CONSTRUCTION. DISCREPANCIES NOT REPORTED ARE THE RESPONSIBILITY OF THE CONTRACTOR. CHECK AND VERIFY ALL DIMENSIONS BEFORE COMMENCING ANY WORK. NOTIFY THE CONTRACT ADMINISTRATOR OF ANY ERRORS OR OMISSIONS.
- 1.5 DO NOT CONSTRUCT FROM THESE DRAWINGS UNLESS MARKED "ISSUED FOR CONSTRUCTION".
- 1.6 ALL COMPONENTS, STRUCTURAL OR OTHERWISE, NOT INCLUDED IN THESE DRAWINGS ARE THE RESPONSIBILITY OF THEIR RESPECTIVE DESIGNER.
- 1.7 READ THESE DRAWINGS IN CONJUNCTION WITH DRAWINGS COMPLETED BY OTHER DISCIPLINES AND CONTRACT SPECIFICATIONS. REPORT ANY DEFICIENCIES TO THE CONTRACT ADMINISTRATOR FOR ALL CONFLICTS BETWEEN PROJECT SPECIFICATIONS AND STRUCTURAL DRAWINGS, INCLUDING STRUCTURAL NOTES. THE STRUCTURAL ENGINEER OF RECORD WILL PROVIDE CLARIFICATION.
- 1.8 NOTIFY THE CONTRACT ADMINISTRATOR A MINIMUM OF 48 HOURS PRIOR TO ANY INSPECTIONS WHERE REQUIRED.

# 2. <u>DESIGN DATA</u>

- 2.1 DESIGN CODE/GUIDELINES:
- CAN/CSA-S7:23 PEDESTRIAN, CYCLING, AND MULTIUSE BRIDGE DESIGN GUIDELINE
- CAN/CSA-S6:19: CANADIAN HIGHWAY BRIDGE DESIGN CODE
- 2.2 DESIGN LIFE: 75 YEARS
- 2.3 SERVICE LIFE FOR NON-REPLACEMENT COMPONENTS: 75 YEARS
- 2.4 DESIGN IMPORTANCE CATEGORY: NORMAL/OTHER ( $l_8 = 1$ ,  $l_w = 1$ ,  $l_e = 1$ )
- 2.5 WIND LOADS (50-YEAR RETURN PERIOD): 0.43 kPa (VERNON, BC)
- 2.6 TEMPERATURE LOADS (50-YEAR RETURN PERIOD):
- MINIMUM MEAN DAILY TEMPERATURE: -35°C
- MAXIMUM MEAN DAILY TEMPERATURE: 30°C
- 2.5 SNOW LOADS (50-YEAR RETURN PERIOD):
- $S_s = 2.2$  kPa
- $S_r = 0.1$  kPa
- 2.6 ICE ACCRETION LOADS: ICE THICKNESS OF 4MM
- 2.7 SEISMIC DESIGN (BASED NATIONAL BUILDING CODE OF CANADA 2020 SEISMIC HAZARDS):
- SITE CLASSIFICATION: SITE CLASS D (BASED ON GEOTECHNICAL REPORT PREPARED BY FLETCHER PAINE ASSOCIATES LTD DATED MARCH 3, 2023)
- IMPORTANCE CATEGORY: OTHER
- SEISMIC PERFORMANCE CATEGORY: 1 (DESIGN EXCEPTION)
- DESIGN RESPONSE SPECTRAL ACCELERATION (SITE CLASS D, 2475-YEAR RETURN PERIOD):
- PGA: 0.104g, Sa(0.2): 0.250g, Sa(0.5): 0.231g, Sa(1.0): 0.177g, Sa(2.0): 0.127g
- 2.8 DESIGN LIVE LOAD:
- PEDESTRIAN LIVE LOAD AS PER CAN/CSA S7:23: 4.25 kPa FOR BOTH BRIDGES
- 80kN MAINTENANCE VEHICLE DESIGN LOAD AS PER S7:23 FOR 16m PEDESTRIAN BRIDGE (IN VICINITY OF CHANNEL STATION 2+210)
- CL-625 DESIGN LOAD WITH DYNAMIC LOAD ALLOWANCE, INCLUDING BRAKING LOADS, AS PER CAN/CSA S6:19 FOR 8m VEHICLE BRIDGE (IN VICINITY OF CHANNEL STATION 1+922)
- 2.9 FATIGUE DESIGN: LESS THAN 50 AVERAGE DAILY TRUCK TRAFFIC PER LANE FOR 8m VEHICLE BRIDGE (IN VICINITY OF CHANNEL STATION 1+922)
- 3. DELEGATED DESIGN
- 3.1 CONTRACTOR IS RESPONSIBLE FOR DESIGN, INSTALLATION AND REMOVAL OF TEMPORARY SHORING, BRACING, FALSEWORK, FORMWORK AND OTHER ERECTION SYSTEMS. DESIGN OF TEMPORARY SHORING, BRACING, FALSEWORK, FORMWORK AND OTHER ERECTION SYSTEMS SHALL BE PREPARED BY AN PROFESSIONAL ENGINEER REGISTERED IN THE PROVINCE OF BRITISH COLUMBIA. CONTRACTOR SHALL SUBMIT SEALED DRAWINGS AND CALCULATIONS OF ALL TEMPORARY WORKS REQUIRED TO COMPLETE CONSTRUCTION TO THE CONTRACT ADMINSTRATOR FOR REVIEW BY THE STRUCTURAL ENGINEER OF RECORD.
- 3.2 CONTRACTOR IS RESPONSIBLE FOR DESIGN AND INSTALLATION OF BRIDGE SUPERSTRUCTURE AND BEARINGS/ANCHORAGE. DESIGN OF BRIDGE SUPERSTRUCTURE AND BEARINGS/ANCHORAGE SHALL BE THE RESPONSIBILITY OF THE BRIDGE MANUFACTURER'S ENGINEER WHO IS A PROFESSIONAL ENGINEER REGISTERED IN THE PROVINCE OF BRITISH COLUMBIA AND FOR THESE COMPONENTS ACT AS THE SUPPORTING PROFESSIONAL OF RECORD. THE CONTRACTOR SHALL SUBMIT SEALED DRAWINGS TO THE CONTRACT ADMINISTRATOR FOR REVIEW BY THE STRUCTURAL ENGINEER OF RECORD. SEALED DRAWINGS SHALL INCLUDE:
- APPLICABLE DESIGN STANDARDS
- DESIGN DATA
- MATERIAL GRADES
- QUALITY CONTROL
- REACTIONS AT BEARINGS FOR THE GOVERNING ULTIMATE LIMIT STATE AS SPECIFIED BY S6:19 AND S7:23 AS WELL AS THE SPECIFIED REACTIONS FOR DEAD LOAD AND LIVE LOAD.
- 3.3 THE BRIDGE MANUFACTURER'S ENGINEER OF RECORD RESPONSIBLE FOR DESIGN OF BRIDGE SUPERSTRUCTURE AND BEARINGS/ANCHORAGE. AS THE SUPPORTING PROFESSIONAL OF RECORD FOR THESE COMPONENTS THEY ARE ALSO RESPONSIBLE FOR REVIEW OF THE FABRICATION AND FIELD REVIEWS FOR THE INSTALLATION OF COMPONENTS IN ACCORDANCE WITH ENGINEERS AND GEOSCIENTISTS BRITISH COLUMBIA PROFESSIONAL PRACTICE GUIDELINES. UPON COMPLETION OF THE WORK CERTIFYING IN WRITING TO THE CONTRACT ADMINISTRATOR THAT SUCH REVIEWS HAVE BEEN COMPLETED.
- 3.4 BRIDGE STRUCTURE DESIGN TO BE COMPLETED IN CONFORMANCE TO PROJECT SPECIAL PROVISIONS FOR PREFABRICATED BRIDGES(S).

- 3.5 BRIDGES SHALL CONFORM TO THE FOLLOWING CRITERIA:
- 8m VEHICLE BRIDGE (IN VICINITY OF CHANNEL STATION 1+922)
- SLAB-ON-GIRDER TYPE BRIDGE
- CONCRETE DECK WITH CONCRETE WEARING SURFACE
- IF PANELS USED FOR DECK, MAXIMUM VERTICAL DIFFERENCE BETWEEN PANELS 3mm WITH MINIMUM LENGTH OF 2.5m.
- DECK TO HAVE A MINIMUM 2% TRANSVERSE CROSSFALL.
- BRIDGE SHALL BE CAMBERED TO HAVE POSITIVE RESIDUAL CAMBER AFTER DEAD LOAD APPLIED.
- TRAFFIC BARRIERS TO MEET TL-1 AS PER S6:19.
- DEFLECTION LIMITS AS PER S6:19 FOR "WITH SIDEWALKS OCCASIONAL PEDESTRIAN USE"
- 16m PEDESTRIAN BRIDGE (IN VICINITY OF CHANNEL STATION 2+210)
- PARALLEL CHORD TRUSS TYPE BRIDGE
- CONCRETE DECK, WITH WEARING SURFACE COATED WITH EPOXY RESIN AND POLYURETHANE AS PER S7:23 CLAUSE 5.9.4.2.
- IF PANELS USED FOR DECK, MAXIMUM VERTICAL DIFFERENCE BETWEEN PANELS 3mm WITH MINIMUM LENGTH OF
- DECK TO HAVE A TRANSVERSE CROSSFALL BETWEEN 1% AND 2%.
- DECK LONGITUDINAL GRADE SHALL BE BETWEEN 1% AND 5% EXCEPT WHERE, FOR LIMITED LENGTHS, VERTICAL CURVE OR SUPER ELEVATION PRECLUDE THIS.
- BRIDGE SHALL BE CAMBERED TO HAVE POSITIVE RESIDUAL CAMBER AFTER DEAD LOAD APPLIED.
- BARRIERS SHALL BE DESIGNED IN ACCORDANCE WITH S7:23 SECTION 5.5 FOR BICYCLES AND PEDESTRIAN TRAFFIC.
- LEVEL OF ACCEPTABLE VIBRATION PER S7:23 PEDESTRIAN INDUCED VIBRATION DESIGN WITH FOLLOWING COMFORT CLASS:

CL2 (MEAN COMFORT)

PEDESTRIAN CLASS (S7:23 TABLE 7.1)

ASSOCIATED MAXIMUM COMFORT CLASS (S7:23 TABLE 7.2)

TC1, TC2, TC3
TC0, TC4, TC5

CL3 (MINIMUM COMFORT)

- 3.6 QUALITY CONTROL FOR PREFABRICATED COMPONENTS SHALL BE PROVIDED TO THE CONTRACT ADMINISTRATOR PRIOR TO INSTALLATION. THE DOCUMENTS SHALL INCLUDE BUT ARE NOT LIMITED TO:
- PROOF OF PLANT CSA CERTIFICATION (WELDING OR PRECAST);
- STEEL MILL TEST CERTIFICATE (OR EQUIVALENT) FOR EACH COMPONENT;
- PLANT REBAR INSPECTIONS PRIOR TO POUR FOR EACH PREFABRICATED CONCRETE COMPONENT; AND
- CONCRETE TEST RESULTS FOR EACH PREFABRICATED COMPONENT.

# 4. FOUNDATION, EXCAVATION, AND BACKFILL

- 4.1 FOUNDATION DESIGN, EXCAVATION, BACKFILL AND COMPACTION ARE BASED ON THE GEOTECHNICAL REPORT "GEOTECHNICAL INVESTIGATION AND REPORT FOR POLSON PARK NATURALIZATION PEDESTRIAN BRIDGES 2600 HIGHWAY 6, VERNON, B.C." PREPARED BY FLETCHER PAINE ASSOCIATES LTD. DATED MAY 08, 2023 AND "ADDENDUM #1 TO MAY 8, 2023 REPORT RE: POLSON PARK NATURALIZATION PEDESTRIAN BRIDGES 2600 HIGHWAY 6, VERNON, B.C." PREPARED BY FLETCHER PAINE ASSOCIATES LTD. DATED JANUARY 29, 2024. ENSURE THAT THE REQUIREMENTS OUTLINED IN THIS DOCUMENT ARE READ AND UNDERSTOOD PRIOR TO COMMENCING FOUNDATION WORK. THIS INFORMATION IS GIVEN SOLELY AS A GUIDE. NO RESPONSIBILITY IS ACCEPTED BY THE OWNER OR CONTRACT ADMINISTRATOR FOR ITS CORRECTNESS NOR SHALL ITS ACCURACY OR ANY OMISSIONS AFFECT THE PROVISION OF THE CONTRACT. FOR FOUNDATION DESIGN BASED ON:
  - ULTIMATE LIMIT STATE BEARING CAPACITY 225 kPa
  - SERVICIBILITY LIMIT STATE BEARING CAPACITY 150 kP
- 4.2 THE CONTRACTOR SHALL ALLOW THE CONTRACT ADMINISTRATOR AND/OR THE OWNER'S GEOTECHNICAL ENGINEER TO INSPECT SOILS DURING EXCAVATION AND SHALL NOT PROCEED WITH THE CONSTRUCTION OF FOUNDATION FORMWORK BEFORE APPROVAL FROM THE CONTRACT ADMINISTRATOR.
- 4.3 THE BEARING SURFACE MUST BE INSPECTED BY THE CONTRACT ADMINISTRATOR PRIOR TO PLACEMENT OF ANY FILL MATERIAL, FOUNDATION FORMWORK, ETC. ANY SOFT OR LOOSE SOILS DETECTED WITHIN THE EXPOSED SUBGRADE, INCLUDING THOSE DISTURBED BY CONSTRUCTION OR OTHER SITE ACTIVITIES, IS TO BE EXCAVATED AT THE DISCRETION OF THE CONTRACT ADMINISTRATOR.
- 4.4 REMOVE ALL EXPOSED ORGANIC MATTER FROM THE EXCAVATION AREA AT THE DISCRETION OF THE CONTRACT
- 4.5 ALL FOUNDATIONS ARE TO BE FOUNDED AT ELEVATIONS AND LOCATIONS SHOWN ON THE DRAWINGS.
- 4.6 PRIOR TO BACKFILL, EXCAVATIONS SHALL BE FREE OF STANDING WATER AND CLEAN OF SHORING MATERIALS, FORMING MATERIALS, TRASH AND DEBRIS. NO SUCH MATERIALS SHALL BE INCLUDED IN THE BACKFILL MATERIAL, ANY LOOSE SOIL SHALL EITHER BE COMPACTED OR REMOVED.
- 4.7 THE LINE OF SLOPE FOR EXCAVATIONS IS NOT TO EXCEED THE VALUES PROVIDED BY THE CONTRACT ADMINISTRATOR AND/OR THE OWNER'S GEOTECHNICAL ENGINEER.
- 4.8 NO BACKFILL SHALL BE PLACED AGAINST THE ABUMENTS UNTIL CONCRETE HAS ACHIEVED ITS 28—DAY DESIGN COMPRESSIVE STRENGTH.
- 4.9 NO PORTION OF BACKFILL IS TO BE PLACED MORE THAN 600mm ABOVE ANY OTHER PORTION OF THE FILL.
- 4.10 ONLY HAND-OPERATED COMPACTION EQUIPMENT SHALL BE USED WITHIN 1.0m OF ABUTMENT AND RETURN WALLS.
  4.11 BRIDGE ENDFILL EXTENTS SHALL BE AS SHOWN ON THE DRAWINGS AND COMPACTED TO 95% OF STANDARD PROCTOR

DENSITY, AT OPTIMUM MOISTURE CONTENT. MATERIAL COMPACTION TESTING MAY BE REQUIRED BY THE CONTRACT

ADMINISTRATOR'S SITE REPRESENTATIVE.

4.12 BRIDGE ENDFILL MATERIAL IS TO BE FREE DRAINING GRANUAL MATERIAL, SUCH AS MMCD GRANULAR PIPE BEDDING AND SURROUND MATERIAL, THAT IS APPROVED BY CONTRACT ADMINISTRATOR'S SITE REPRESENTATIVE PRIOR TO ALL BACKFILLING OPERATIONS.

# 5. CONCRETE

- 5.1 CONCRETE DESIGNED, TESTED, AND HANDLED TO CAN/CSA A23.1 AND CAN/CSA A23.2.
- 5.2 CAST-IN-PLACE CONCRETE MIX DESIGN SHALL BE DESIGNED FOR CLASS F-1 EXPOSURE, WITH MINIMUM 28-DAY COMPRESSIVE STRENGTH OF fc' = 30MPa
- 5.3 SUBMIT CONCRETE MIX DESIGNS AS SHOP DRAWINGS FOR REVIEW. EACH CONCRETE MIX DESIGN SUBMITAL SHALL INCLUDE:
- NAME OF THE PROPOSED SUPPLIER
- PROJECT SPECIFICES
- DISTANCE AND EXPECTED TRAVEL TIME FROM BATCH PLANT TO PROJECT SITE
- EXPECTED METHOD OF BATCHING, TRANSPORTATION AND PLACEMENT OF CONCRETE
- SPECIFIED MIX PARAMETERS REQUIREMENTS
- NAME AND CONTACT INFORMATION OF INDEPENDENT, CERTIFIED QUALITY CONTROL TESTING FORM AND/OR CERTIFIED TESTING PERSONNEL
- 5.4 MINIMUM 14 DAYS PRIOR TO STARTING CONCRETE WORK SUBMIT TO CONTRACT ADMINISTRATOR MANUFACTURER'S TEST DATA AND CERTIFICATION BY QUALIFIED INDEPENDENT INSPECTION AND TESTING LABORATORY THAT MATERIALS WILL MEET SPECIFIED REQUIREMENTS AS PER CONTRACT SPECIFICATIONS. PROVIDE TO CONTRACT ADMINISTRATOR CERTIFICATION THAT PLANT, EQUIPMENT, AND MATERIALS TO BE USED IN CONCRETE COMPLY WITH REQUIREMENTS OF CAN/CSA A23.1. PROVIDE TO CONTRACT ADMINISTRATOR CERTIFICATION THAT SUBMITTED MIX DESIGN WILL PRODUCE QUALITY, DURABILITY, AND STRENGTH WILL COMPLY WITH CAN/CSA-A23.1.
- 5.5 ALL EXPOSED EDGES OF CONCRETE SHALL BE CHAMFERED 20 MM UNLESS OTHERWISED NOTED.
- 5.6 FORMWORK SHALL BE DESIGNED, SUPPLIED, AND INSTALLED IN COMPLIANCE WITH CAN/CSA-S269.1
- 5.7 WHERE NEW CONCRETE IS TO BE PLACED AGAINST EXISTING CONCRETE, EXISTING CONCRETE IS TO BE ROUGHED TO AN AMPLITUDE OF 6mm AND CLEANED TO THE SATISFACTION OF THE CONTRACT ADMINISTRATOR. CLEAN SURFACES OF ALL CONSTRUCTION JOINTS THOROUGHLY AND REMOVE LAITANCE.
- 5.8 BEFORE PLACING CONCRETE, ENSURE THE REINFORCING STEEL AND FORMS ARE CLEAN OF ALL LOOSE SCALE, DIRT, CORROSION, OR OTHER FOREIGN MATEIRAL WHICH COULD REDUCE BOND BETWEEN REINFORCEMENT AND CONCRETE.
- 5.9 PRIOR TO ANY CONCRETE POURS THE CONTRACTOR SHALL ARRANGE FOR AN INSPECTION BY THE CONTRACT ADMINISTRATOR OR THEIR REPRESENTATIVE TO VERIFY CONFORMANCE OF FORMWORK AND REINFORCEMENT TO CONTRACT REQUIREMENTS.

# 6. REINFORCEMENT

- 6.1 REINFORCING STEEL SHALL CONFORM TO CAN/CSA-G30.18 GRADE 4002, UNLESS NOTED OTHERWISE.
- 6.2 SPACING OF BARS SHOWN ON THE DRAWINGS IS FROM CENTER-TO-CENTER IN THE DRAWINGS.
- 6.3 WELDING OF REINFORCING STEEL IS NOT PERMITTED.
- 6.4 GALVANIZED COMPONENTS EMBEDDED IN CONCRETE SHALL NOT BE IN DIRECT CONTACT WITH REINFORCING BARS.
- 6.5 MINIMUM LENGTH OF LAP SPLICES FOR ALL REINFORCING BARS SHALL BE AS FOLLOWS UNLESS OTHERWISE NOTED:

	SPLICE LAP TABLE	
BAR SIZE	TYPICAL BARS	TOP BARS *
15M	550	670
20M	680	890
25M	1070	1390

SPLICE LENGTH ASSUME CLASS B TENSION SPLICES. BAR IS CONSIDERED A "TOP BAR" IF MORE THAN 300 mm OF FRESH CONCRETE IS CAST BELOW THE BAR.

6.6 MINIMUM DEVELOPMENT LENGTH FOR ALL REINFORCING BARS SHALL BE AS FOLLOWS (mm):

DEVELOPMENT LENGTH TABLE				
BAR SIZE	TYPICAL BARS	TOP BARS *		
15M	420	510		
20M	530	680		
25M	820	1070		

- 6.7 MECHANICAL SPLICES ARE NOT PERMITTED.
- 6.8 MINIMUM CONCRETE COVER TO REINFORCEMENT AND ASSOCIATED TOLERANCES SHALL BE AS FOLLOWS (mm):

EACH FACE

- SURFACES CAST AGAINST EARTH 100  $\pm$  25
- ALL OTHER SUFACES 70 ± 20
- 6.9 ATTACHMENTS AND ANCHORAGES SHALL NOT BE IN CONTACT WITH REINFORCEMENT 6.10 REINFORCEMENT LOCATION ABBREVIATIONS:
- I.F. INSIDE FACEO.F. OUTSIDE FACE
- 7. RIPRAP

• E.F.

7.1 REFER TO DRAWING NUMBER GOO4 FOR RIPRAP NOTES.

# 8. ENVIRONMENTAL

8.1 REFER TO DRAWING NUMBER GOO4 FOR ENVIRONMENTAL NOTES.





SCALE AS NOTED


BRIDGE GENERAL NOTES - PHASE 2


POLSON PARK NATURALIZATION


1 of 3 REACH 1


DRAWING NUMBER


S101












PHASE 2

ENGINEERING AND GIS SERVICES

29.01.2







SCALE
<b>H:</b> 1:200 <b>V:</b> –

LANDSCAPE PLANTING CHANNEL PLAN — CENTRAL

SHEET POLSON PARK NATURALIZATION
4 of 5 PHASE 2

